

CITY OF LAFAYETTE
STANDARD SPECIFICATIONS
TECHNICAL PROVISIONS

**SECTION 1
MOBILIZATION**

1-1 GENERAL - Mobilization shall consist of preparatory work and operations, including but not limited to:

- 1) Provision of all required bonds.
- 2) Movement of personnel, equipment, supplies, and incidentals to the project site.
- 3) Establishment of all offices, buildings and other facilities necessary for work on the project. *Contractor's attention is directed to requirement of sanitary restroom facilities in Section 6-2 of the General Provisions.*
- 4) Public notifications.
- 5) Fabricating and installing Project Identification Signs per detail on following page.
- 6) All other work and operations which must be performed or costs incurred prior to beginning work on the various contract items on the project site.
- 7) Demobilization

1-2 PROJECT IDENTIFICATION SIGN

1-2.1 General - Signs shall be furnished by City. At least 48 hours prior to commencement of construction, the Contractor shall erect project identification signs at the locations as indicated on the Plans or as directed by Engineer.

1-2.2 Materials - Signs furnished by City will measure 36" x 48". Posts for mounting to be furnished by Contractor shall be 4" x 4" unpainted, construction grade redwood. Where post installation is not feasible, Contractor may mount signs on Type III barricades if approved in advance by the Engineer.

1-2.3 Installation, Maintenance, and Removal - The Contractor shall be responsible for installing and erecting the signs as required to serve the intended use. Contractor shall maintain and protect signs in good condition throughout the duration of Project. Upon completion, Contractor shall remove signs and return them to City. If at any time the signs are damaged due to Contractor's lack of effort or negligence in maintaining, protecting, or handling signs, Contractor shall be responsible for the cost of fabricating replacement signs in-kind. City shall deduct said cost from any money due to Contractor under Contract.

1-2.4 Measurement - Project identification signs shall be measured on a per each basis.

1-2.5 Payment - The Contract Unit Price paid for Project Identification Signs shall be considered as including full compensation for installing, maintaining, protecting, and removing project signs, including posts, barricades, and miscellaneous hardware for mounting, and all incidental work involved, and no additional compensation shall be allowed therefor.

1-3 CONSTRUCTION AREA SIGNS

1-3.1 General - Construction area signs shall conform to Section 12-3.06 of the State Specifications. Signs shall be stationary mounted and shall be maintained throughout the life of the project. When no longer required, they shall be removed. Contractor shall notify Underground Service Alert (USA) at 1.800.227.2600 at least 48 hours prior to commencing excavation for sign posts. All excavations to install signs shall be by hand without the use of power equipment.

1-3.2 Panels and Posts - Signs shall be metal with reflective coating, black on orange, and mounted on 4"x4" wood posts or Type III barricades. Signs shall be kept clean and in good repair.

1-3.3 Measurement - Construction area signs shall be measured on a per each basis.

1-3.4 Payment - The Contract Unit Price paid for Construction Area Signs shall be considered as including full compensation for fabricating, installing, maintaining construction area signs, including but not limited to their maintenance and removal upon completion of the project.

1-4 MEASUREMENT

Except for constructing and installation of project signs as provided above, mobilization will be measured on a lump sum basis.

1-5 PAYMENT - Except for the fabrication and installation of project signs as provided above, payments for mobilization will be made with each progress payment on a prorated percentage basis or other such basis as approved by the Engineer. The prorated basis shall be the total for the progress billing divided by the total contract amount, adjusted in accordance with approved change orders.

The contract lump sum price paid for mobilization shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals, and for doing all the work involved in mobilization as specified herein, and no additional compensation shall be made therefor. Mobilization shall be considered as a non-adjustable contract item. Any contract change orders shall be considered as including full compensation for mobilization.

When the contract does not include a contract pay item for mobilization as above specified, full compensation for any necessary mobilization required shall be considered as included in the prices paid for the various contract items of work involved and no additional compensation will be allowed therefor.