

**MANZANITA ROOM
CITY OF LAFAYETTE COMMUNITY CENTER
500 SAINT MARY'S ROAD
LAFAYETTE, CA 94549**

PROJECT NO. 012-9174

DOCUMENT 00 91 13

ADDENDUM NO. 4


The following clarifications, additions, and deletions shall become a part of the plans and specifications for the above project, and shall be bound by the General Conditions, Technical Specifications, and all other conditions of the Bid Documents.

PROJECT MANUAL

Part 1 "General," Section 1.04 "Work Sequence," Paragraph A- The order of major construction items is amended to read as follows:

1. Notify others regarding project construction as required by Contract.
2. Install security fencing and tree protection measures.
3. Implement stormwater pollution measures.
4. Clear and grub site; salvage items required by Contract.
5. Demolish building.
6. Perform rough grading.
7. Install underground facilities (See also Paragraph B).
8. Construct foundation and pad.
9. Construct building, appurtenances, and site improvements.
10. Perform final cleaning, system demonstration, and job close-out.

CITY OF LAFAYETTE



Date: September 16, 2014

By: Tony Coe, City Engineer