2020 Road Resurfacing Project

Project Time Line:

Total Estimated Project Construction Cost \$2,200,000

Bid Opening July 7th

Road Construction Project Begins Early August

Anticipated Completion Late October

The City of Lafayette will issue a single contract to reconstruct the following streets:

Acalanes Road Saint Mary's Road Beechwood Drive Reliez Valley Road

The construction timeline will be longer than what would be required for just the work on a single street. Please expect to see work occurring in phases, with potentially large gaps of inactivity in between while the construction crew shifts to similar work at another location.

In order to better inform the public about the project status, weekly updates will be posted on the City's website at http://www.ci.lafayette.ca.us (select *Public Works & Construction* link followed by *City Construction Projects* followed by *2020 Road Resurfacing Project*). These updates will provide information on the work scheduled for the following week and how it will impact access to various streets.

Summary of Major Work Items:

All of the work described below will occur within the City's right-of-way or easements. None of the work will occur on private property. The City's right-of-way typically extends ten feet (or more) beyond the back of curb or edge of pavement into what you may consider portions of your front yard.

Bushes, shrubs, and trees that have grown out past the existing or design edge of pavement will be trimmed back to a point 1 foot behind the new edge of pavement and to 14 feet above the road. In the case of some plants like juniper bushes, this may expose the bare interior of the bush. If you are concerned about the methods to be used in trimming your vegetation, please consider doing the work yourself in advance of the project. Again, please be reminded that these items are currently on public property.

Acalanes Road

- 1. Spot repairs will be made to the existing asphalt pathway from Black Forest Court to Hidden Valley Road.
- 2. Repairs will be made to the guard rail system including closing the gaps across from Legion Court
- 3. The road alignment will be shifted to the south at 863 Acalanes Road to pull the traveled lane away from the existing drainage ditch and utility pole. This work will require a corresponding realignment of the pathway on the south side of the road.
- 4. Spot repairs and crack filling will be performed from Coralee Lane to Mount Diablo Bouelvard
- 5. The road will be repayed with approximately 2-inches of asphalt from Black Forest Court to Hidden Valley Road
- 6. The road will be restriped

Saint Mary's Road

- 1. Spot repairs and crack filling will be performed from Moraga Road to Glenside Drive
- 2. The road will be repayed with approximately 2-inches of asphalt from Hope Lane to Glenside Drive
- 3. Asphalt berms that are removed as part of the repaving process will be replaced
- 4. The road will be restriped

Beechwood Drive

- 1. A storm drain system will be installed between 3303 Beechwood Drive and the existing storm drain crossing at 3291 Beechwood Drive. This new system will replace the existing driveway and ditch system that currently exists.
- 2. The driveway culverts at 3207 and 3303 Beechwood Drive will be replaced and the existing ditch will be regraded and vegetation removed from the ditch area.
- 3. The existing edge of pavement from 3315 Beechwood Drive to 3207 Beechwood Drive will be profiled to allow water to flow along the South side of the street to the ditch and storm drain system rather than crossing the street.
- 4. Spot repairs and crack filling will be performed from Hawthorne Drive to Reliez Station Road
- 5. The road will be repaved with approximately 2-inches for asphalt from Hawthorne Drive to Reliez Station
- 6. The existing speed bumps will be removed and replaced in the same location
- 7. Asphalt berms that are removed as part of the repaving process will be replaced. The low berms, not at driveways from 3260 Beechwood Drive to Reliez Station Road will be replaced with 6-inch tall berms.
- 8. The road will be restriped

Reliez Valley Road

- 1. Handicap ramps will be constructed at Angelo Street, La Caminita, Silver Dell Road, Shangri La Road, and Echo Springs Road.
- 2. Spot repairs and crack filling will be performed from McGraw Lane to Withers Avenue
- 3. The road will be repayed with approximately 2-inches for asphalt from Rossi Street to Echo Springs Road
- 4. Asphalt berms that are removed as part of the repaving process will be replaced.
- 5. The road will be restriped

Resident Homework:

- 1. In most cases residents have a sewer lateral out to the sewer main in the middle of the street. As such the City is requesting that residents who have not replaced their sewer lateral within the last 5 years consider having their line inspected, and if necessary replaced, prior to July 31st. This work will require an encroachment permit from the City. However, if the work is completed prior to the above date, the City will waive our usual permit fees. If a road cut is made after the project, the street restoration requirements will be exceptionally onerous, and expensive.
- 2. If you have frontage landscaping that is of special importance to you, or irrigation, lighting, drain lines, or other improvements within the public right of way, please let the Engineering Services Manager, Matt Luttropp, know about these items at your earliest opportunity to coordinate their preservation where possible.

Contact Information

Matt Luttropp, Engineering Services Manager City of Lafayette, PH #299-3247, Email: mluttropp@ci.lafayette.ca.us