

**Lafayette Library & Learning Center
Children's Activity Deck Remodel
3491 Mt. Diablo Blvd.
Lafayette, CA 94549**

PROJECT NO. 037-770-906

ADDENDUM NO. 2

The Contract Documents are clarified and/or modified by this addendum and shall become a part of the plans and specifications for the above project, and shall be bound by the General Requirements, Technical Specifications, and all other conditions of the Bid Documents.

1. The following are required as part of the design/build sprinkler system:
 - New sprinkler piping routing to be concealed above the existing library ceiling panels.
 - The perimeter PSL beam and exterior metal panels shall not be penetrated. Routing shall occur above the PSL.
 - Routing shall continue concealed within the existing exterior soffit until it reaches the new trellis.
 - Any exposed piping shall be painted to match the adjacent material finishes.
 - All cut and/or removed materials shall be replaced in kind, see Section 01 73 29, "Cutting and Patching".
 - All routing shall be reviewed and confirmed with the Engineer prior to submittal of the drawings to the Fire Department for approval.

2. The original drawings for the existing building sprinkler system are provided for reference only; all conditions must be verified in the field. (To view the drawings, click [here](#) or contact tkain@lovelafayette.org to have the link sent to you.)

CITY OF LAFAYETTE



Date: April 07, 2021

By: Farzaneh Sanders, Senior Engineer